


**HRC**  
**HUBBELL, ROTH & CLARK, INC**  
 CONSULTING ENGINEERS SINCE 1915  
 105 W. GRAND RIVER AVE.  
 HOWELL, MI 48843  
 PHONE: (517) 552-6199  
 FAX: (517) 552-6099  
 WEB SITE: <http://www.hrc-enr.com>

7-10-17	ADDENDUM NO. 2
6-12-17	ISSUED FOR BIDS
3-3-17	PRELIMINARY PLAN SUBMITTAL
DATE	ADDITIONS AND/OR REVISIONS
DESIGNED	D.H./P.K.
DRAWN	D.H./K.W.
CHECKED	A.E.M.
APPROVED	



**NOTES**

- PAVEMENT REPAIR WORK AT THIS LOCATION IS TO APPLY ONLY TO THE LIMITS SHOWN ON THIS PLAN SHEET.
- THE REMOVAL OF THE EXISTING HMA (+/- 4" THICK) WILL BE PAID FOR AS "COLD MILLING HMA SURFACE" - SYD.
- THE NEW CROSS SECTION AT THIS LOCATION WILL BE 4 INCHES OF HMA, 13A PLACED IN TWO LIFTS AND PAID FOR AS "HMA, 13A, 2 INCH, SPECIAL" - SYD ON EXISTING AGGREGATE BASE. SHOULD ADDITIONAL AGGREGATE BE NECESSARY, CONTRACTOR TO SUPPLEMENT WITH "AGGREGATE BASE, SPECIAL" - TON. "EXCAVATION, EARTH" WILL BE PAID FOR THE REMOVAL OF THE EXISTING AGGREGATE, SHOULD ANY BE NECESSARY. BOTH OF THESE QTY'S WILL BE PAID ON AN AS-DIRECTED BASIS.
- CONSTRUCTION LIMITS TO NOT GO BEYOND EXISTING EDGE OF METAL CURB AND GUTTER TO REMAIN AND NO WORK TO OCCUR IN DRIVEWAYS.

**QUANTITIES - THIS SHEET (FOR INFO ONLY)**

PAY ITEM	QTY	UNIT
Cold Milling HMA Surface	1,802	Syd
HMA, 13A, 2 inch, Special	3,604	Syd
Reclamite, Special	1,802	Syd

**LEGEND**

MILL, OVERLAY AND RECLAMITE

QUANTITY LIMITS

NOTE: UTILITY INFORMATION ON THIS DRAWING MAY BE FROM INFORMATION DISCLOSED TO THIS FIRM BY THE VARIOUS UTILITY COMPANIES, CITY/COUNTY AGENCIES AND OTHER VARIOUS SOURCES. UNDERGROUND UTILITIES WHICH ARE ON PRIVATE PROPERTY ARE USUALLY NOT DELINEATED UPON A UTILITY COMPANY'S PUBLISHED PLANS. THEIR LOCATION, IF SHOWN UPON THIS SURVEY, ARE APPROXIMATED FROM FOUND PAINT MARKS/STAKES, ETC. AS LOCATED BY THIS FIRM FROM SOURCES WHICH ARE UNKNOWN. NO GUARANTEE IS GIVEN AS TO THE COMPLETENESS OR ACCURACY THEREOF.

PRIOR TO CONSTRUCTION, ALL LOCATIONS AND DEPTHS OF EXISTING UTILITIES (IN CONFLICT WITH PROPOSED IMPROVEMENTS) SHALL BE VERIFIED IN THE FIELD. CALL MISS DIG 3 WORKING DAYS PRIOR TO CONSTRUCTION.



THREE FULL WORKING DAYS BEFORE YOU DIG, CALL THE MISS DIG SYSTEM AT 800-482-7171 OR 811.

**CITY OF HOWELL**  
**2017 PAVING IMPROVEMENTS**

**CLINTON ST. PAVEMENT REPAIR**

HRC JOB NO. 20160036	SCALE N/A
DATE June 2017	SHEET NO. 15 OF 27